

**BHARAT COKING COAL LTD.**  
**OFFICE OF THE GENERAL MANAGER**  
(A subsidiary of Coal India Limited)

Chanach Victoria Area-XII

Ref.No. : E&M/XII/BCCL/NIT/09-10 /298-318

Date: 13/02/10

**Notice Inviting Tender**

Sealed tenders are invited from Experienced and bonafide Contractor/Agency for the under noted work. The tender should be submitted in two part that is, Part-I containing Tech-Commercial bid and Part-II containing Price bid, Part-I and Part-II envelope must be super scribed and sealed. Sealed Part-I & Part-II envelope must be sealed in a third envelope.

Tenders must reach the office of the undersigned latest by 05.03.10 up to 1:00 P.M. and Tech-Commercial bid will be opened on the same day at 3:00 P.M.

Sl. No.	Name of work	Estimated Cost Rs.	Tender Cost Rs.	Earnest Money Rs.	Time of Completion
1.	Extension of 220 V O/H line from Kalyanchak 'A' Coal Depo of DBOCP	2,92,474/-	Rs. 100/- + Tax	Rs. 2,930/-	10 Days
(Non-refundable) (Refundable)					
Tender issued on 22.02.10 to 04.03.10					

**Terms & Conditions:-**

1. Tender Paper can be obtained from the office of the undersigned on any working day on production money receipt for the Cost of Tender paper (Non-refundable).

2. Earnest money as mentioned should be deposited either in the form of Bank draft drawn in favour of BCCL, A-XII, payable at Barakar or may be deposited in Cash with Finance Dept., upto 1:00 P.M. on week days and money receipt in original is to be submitted alongwith the offer, without E.money no tender will be accepted.

**3. Other Requirements:-**

(a) PAN CARD (ZEROX) (b) Vat (Upto date) (c) E.Money receipt in original (d) Time of completion (e) Validity of Tender should be 120 days from the date of opening of price bid (f) Guarantee period minimum six months after installation (g) Valid Contractor License with Supervisory certificates for power line jobs applicable, (H.T/L.T as applicable). (h) Service Tax Registration copy (i) Deed of Partnership, Residential proof and proof of commencement of business. (j) All documents should be self attested with date & seals. (k) Desirable Experience Credential.

The intending bidders must have in his name and experience and having successfully completed Electrical O/H Line in BCCL or any other public sector undertaking or Govt. firm in during last 7 yrs ending last day of the month previous to the one in which bid application are invited, should be either of the following:-

(i) Three similar completed works each costing not less than the amount equal to 40% of the estimated cost Or

(ii) "Two" similar completed works each costing not less than the amount equal to 50% of the estimated cost. Or

(iii) One similar completed works each costing not less than the amount equal to 80% of the estimated cost.

4. 10% security money including the Earnest Money will be deducted from the final bill till completion of completion period.

5. Please send authorized representative for Tender paper collection etc.

6. Management reserves the right to accept or reject the tender or part there of without assigning any reasons whatsoever.

Area Manager(E&M)  
BCCL;C/V Area-XII,

Distribution:-

1.P.M.(Admn.), C.V. Area for display in Notice Board.

2. All AM. (E&M), – Area- I to XII.

3. All Colly.Engr (E&M) C/V Area.

4.Addl. G.M. , C/V Area.

5. A.F.M., C/V Area.

6. Cashier ; C.V. Area, for cost paper/E.Money.

7. Tender file.

8. Manager Publication P\_R\_ Division, Koyla Bhawan.

**BHARAT COKING COAL LIMITED**

Chanch Victoria Area-XII

Tender Paper

Ref No. :- E&M/XII/BCCL/NIT/09-10 /298-318

Dt.13/02/10.

Name of work:- Extension of 220 V. O/H Line for Kalyanchak 'A' Coal Depo of DBOCP.

<u>Sl.No.</u>	<u>Qty.</u>	<u>Rate</u>	<u>Amount</u>
1. Erection of Pole Tubelor/P.C.C. upto 11 mtrs but not exceeding 13 mtrs. Incl. earth digging& refilling etc. as reqd (Pole BCCL supply).	10 Nos		
2. Supply of cement, sand, stone chips for cement concreting 1:3:6 (1 cement 3 coarse Sand, 6 graded stone chips aggregate 40mm nominal size) 1.5 cum.	10 Nos		
3. Supply & erection of Galv. Stay set with earth digging as reqd. with 19/20mm dia x 1.8 mtrs long stay rod, Anchor Plate of thick size 45cm x 45cm x 7.5mm thick Thumbles comp. incl. supply of cement, Sand, Stone Chips for its concreting with G.I. Stay Wire, Stay/Guy Insulator etc.	10 Nos		
4. Supply & erection of 110mm x 100mm Dia Shackle /Pin Insulator of ISI quality.	28 Nos		
5. Supply, fabrication, erection & painting from Red Oxide of Iron & steel materials such as Cross arms Bracing, various sizes of clamps incl. suitable size nut, bolts, washer etc.	380 kgs.		
6. Supply & erection of earth continuous earth wire from 7/16 SWG/8 No.SWG G.I. Wire for earth continuity.	150 Mtrs		
7. Laying & stringing of AAAC/ACSR Rabbit Conductors with Sag incl. jumphereing & Binding etc.	185 kgs.		
8. Supply, & Erec. Of 250W x 220V sodium Vapour comp. set with fixing in the top of pole Incl. Fabrication of Swan type 2" G.I. Pipe PVC Wire clamp, nuts, bolts, washer etc.	8 Nos		

8. a) Supply, Erection of 400W x 220 Volts sodium vapor comp. set with fixing in the top of pole including fabrication of swan type 2" G.I. pipe PVC wire clamp, nuts, bolts, washer etc.	5 Nos
9. Transporting of Pole from Workshop to Works Site.	10 Nos
10. Supply & erection of 60 Amps ICDP Main Switch for controlling of light.	1 No.
11. Earthing as per I.E. Rule with earth cutting with refilling Salt, Pipe & Charcoal etc.	2 Nos
12. Laying of cable from 220V O/H Line to Light for Service connection.	20 Mtrs.
13. Dismantling of existing damage line ACSR Conductor for making of Coil with Bracket, Insulator etc.	385 kgs.
14. Dismantling of Pole & Pipe Conductor and other materials.	L.S.
15. Check, Survey & Pag marking, making of approach road and Line Testing, charging complet.	L.S.

Total Rs.

(Rupees-----

----- only).

Signature of issuing authority  
Contractor

C/V Area

Signature of

with seal & date.

